	Basic Rate	293.00						
	Area Weightage 8%	23.44						
	Total	**316.44**						
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading **Page No. 150 Item No. 17.1 PWD SR 2013-14**	Cum						
			Qty Vide Item No. 1			**381.00**	78.24	29808.00
	2 x 1.28 x 4 Kmtrs	10.24						
		62.20						
	Basic Rate	**72.44**						
	Add Area Weightage 8%	5.80						
	Total	**78.24**						
14	Miscellaneous and Unforeseen Charges etc.., complete	LS						3729.00
							Total	**2000000.00**

(Rupees Twenty Lakhs Only)

CERTIFICATE

1) The Work spot has been inspected and the work is found to be necessary
2) The Estimate is prepared as per the PW,P & IWTD - SR - 2013-14
3) The Provision made in estimate are adequante and essential
4) This area comes under B.B.M.P Limits.

Assistant Engineer
Ward No.14

Asst.Executive Engineer
T.Dasarahalli Sub-Division
B.B.M.P. Bangalore.

Executive Enginee
Dasarahalli Divisio
B.B.M.P. Bangalor

CE/D.K/78

ನಂ. 29/15.16 ದಿನಾಂಕ 4-1-2016

ರೂ. 20.00 ಲಕ್ಷ